BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/03/2018-19 Dt: 01-12-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 03

Name of Work:-Emergency works in ward no 2 of yelahanka sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Sri. G MUNIRAJU (K B S ENGINEERING WORKS)	
				Rate	Rate in Words
1	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bankor on the canal embankment in layers as directed etc., complete withinitial lead upto 50 m and all lifts. MISR 2014-15 Page No 131 item No 51	cum	1476.00	147.00	Rupees One Hundred Forty Seven Only
2	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no143, PWD SR 2018-19)	cum	109.00	137.00	Rupees One Hundred Thirty Seven Only
3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 136 (SR 2018-19)	cum	1585.00	87.00	Rupees Eighty Seven Only
4	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)/ PWD SR 2018-19	Cum	16.3500	5408.00	Rupees Five Thousand Four Hundred Eight Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Sri. G MUNIRAJU (K B S ENGINEERING WORKS)	
				Rate	Rate in Words
	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Ite mo 37.59.2 SR 2018-19	Cum	48.60	7070.00	Rupees Seven Thousand Seventy Only
6	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	3.27	75224.00	Rupees Seventy Five Thousand Two Hundred Twenty Four Only
7	RCC Precast covering slab for drain (10cm thick)	sqm	100.80	2100.00	Rupees Two Thousand One Hundred Only
8	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge-	sqm	28.80	5111.00	Rupees Five Thousand One Hundred Eleven Only
9	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete. Page No. 27/ Item No. 5.29/ PWD SR 2018-19	Nos	778.00	477.00	Rupees Four Hundred Seventy Seven Only
10	Engaging on Hire Basis JCB including Driver/operator with fuel etc complete (SR 2018-19) Page No XLVIII code 1031) Sl No 23	Day	8.00	5695.00	Rupees Five Thousand Six Hundred Ninety Five Only
11	Engaging on Hire basis of Tractor 50 HP for Conveying of excavated and removal of Stuff from work spot (SR 2018-19) Page No XLVIII code 1024) Sl No 23	Day	85.00	2512.00	Rupees Two Thousand Five Hundred Twelve Only
12	Labour charges to Unskilled Mazdoor Heavy (Page no .LIV)SR 2018-18 sl No 5	Day	680.00	446.00	Rupees Four Hundred Forty Six Only
13	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	Cum	562.50	188.00	Rupees One Hundred Eighty Eight Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Sri. G MUNIRAJU (K B S ENGINEERING WORKS)	
				Rate	Rate in Words
14	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	Rmtr	1250.00	156.00	Rupees One Hundred Fifty Six Only
15	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	Cum	562.50	60.00	Rupees Sixty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.